



CONSTRUCTION NOTES:

1. CONTRACTOR TO PROTECT ALL TREES SHOWN ON PLANS OR DESIGNATED BY OWNER TO REMAIN IN THE BEST POSSIBLE MANNER TO INSURE THE TREE'S SURVIVABILITY.
2. KEEP ALL CONSTRUCTION OPERATIONS AS FAR FROM EXISTING TREES AS PRACTICAL. PREVENT DUMPING AND BURNING AROUND EXISTING TREES.
3. CONTRACTOR TO PROTECT AREA WITHIN TREE DRIPLINE (TREE CANOPY) FROM:
 - a) SUPPLIES AND EQUIPMENT STORED UNDER TREE CANOPIES.
 - b) VEHICULAR AND FOOT TRAFFIC COMPACTION.
 - c) GRADE CHANGES OF 4" CUT OR FILL.
 - d) UNNECESSARY UTILITY EXCAVATION.
 - e) SITE CLEARING AND GRADING OPERATIONS.
 - f) DUMPING OF CHEMICALS, PAINTS OR OTHER TOXIC MATERIALS.
4. CONTRACTOR TO REPLACE OR PROVIDE ADEQUATE COMPENSATION FOR TREES SHOWN ON PLANS OR DESIGNATED BY OWNER TO REMAIN WHICH ARE REMOVED OR HEAVILY DAMAGED AS A RESULT OF CONSTRUCTION OPERATIONS.
5. CONTRACTOR TO USE FOLLOWING CONSTRUCTION PROCEDURES UNDER TREE DRIP LINE:
 - a) PROTECT TREE TRUNK WITH 8' ht. 2 x 4 TREE BOARDS COMPLETELY AROUND TRUNK. WRAP, DO NOT NAIL, AROUND TREE.
 - b) PROMPTLY PRUNE AND TREAT ANY EXPOSED ROOTS OVER 3/4" DIAMETER.
 - c) FILL ALL UTILITY TRENCHES AS SOON AS POSSIBLE.
 - d) CONTACT CITY OF LAMPASS PRIOR TO CONSTRUCTION IF GRADING MORE THAN 5" FILL OR CUT UNDER DRIP LINE.

DETAIL DEPICTS DIMENSIONAL REQUIREMENTS. THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS STANDARDS.



TREE PROTECTION
PLASTIC FENCE

STANDARD CONSTRUCTION DETAILS
CIVIL

DATE:
MARCH 2007

SCALE:
NTS

SHEET:
SD-EV07