



GENERAL NOTES:

1. MATERIALS AND CONSTRUCTION METHODS SHALL CONFORM TO STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION.
2. #4 REBARS ENTIRE LENGTH OF CURB, PROVIDE DOWELS AT EXPANSION JOINTS.
3. EXPANSION JOINTS SHALL BE INSTALLED AT INTERVALS NOT TO EXCEED 40 FEET.
4. CONSTRUCTION JOINTS TO BE TOOLED EVERY 10 FEET MAX.

DETAIL DEPICTS DIMENSIONAL REQUIREMENTS. THE ARCHITECT/ENGINEER ASSUMES RESPONSIBILITY FOR THE APPROPRIATE USE OF THIS STANDARDS.



CURB & GUTTER SECTION

STANDARD CONSTRUCTION DETAILS  
PAVING

DATE:  
MARCH 2007

SCALE:  
NTS

SHEET:  
SD-P08